
SLOTTED RAIL TERMINAL 6 POST SYSTEM



	BILL OF MATERIAL			
	PC	QTY	DESCRIPTION	
	3G	1	12/12"/BACKUP (GUARDRAIL)	
	9G	1	12/12'6/6'3/S (GUARDRAIL)	
	30G	1	12/12'6/S SRT-1 (GUARDRAIL)	
	39G	1	12/12'6/S SRT-2 (GUARDRAIL)	
	700A	1	CABLE ANCHOR BRACKET	
	907G	1	12/BUFFER/ROLLED (TERMINAL)	
	3000G	1	3/4 x 6'6" CABLE	
	3300G	14	5/8" WASHER	
q	3340G	58	5/8" HEX NUT	
	3360G	44	5/8"0 x 1 1/4" SPLICE BOLT	
	3380G	8	5/8"Ø x 1 1/2" HEX HD BOLT	
	3400G	2	5/8"Ø x 2" POST BOLT	
	3580G	4	5/8″Ø x 18″ POST BOLT	
	3701G	10	3/4" WASHER	
	3704G	4	3/4" HEX NUT	
	3718G	4	3/4"Ø x 3" HEX HD BOLT (A325)	
	3900G	1	1" WASHER	
	3910G	2	1" HEX NUT	
	4063B	4	6' POST 6" x 8"	
	4075B	4	14" BLOCK 6" × 8"	
	4254G	5	3/8" WASHER	
	4258G	4	3/8" LOCKWASHER	
	4261G	1	3/8"Ø x 1 1/2" HEX HD BOLT (GR 5)	
	4699G	4	3/4" LOCKWASHER	
	6321G	4	3/8"Ø x 2" HEX HD BOLT (GR 5)	
	6405G	5	3/8" HEX NUT	
	9960G	4	SLOT GUARD	
	9961G	1	3/8" x 3" x 4" PLATE WASHER	
	33876A	1	HBA POST 1 TOP (W6 x 8.5)	
	33877A	1	HBA POST 2 TOP (W6 x 8.5)	
	33878A	2	HBA POST 1 & 2 BOT (TS 6 x 4)	
	33879G	2	ANGLE STRUT 2" x 2" x 3/8"	
	33880G	1	1" × 6" × 8" BEARING PLATE	
	33881G	1	CABLE WEB PL 4" x 1/4" x 6 1/2"	
		' '	CAULL HED FL 4 X 1/4 X 0 1/2	

€p

DETAIL "G" (@ POST #1)

- GENERAL NOTES: 1. Wood posts are required with the slotted rail terminal except posts 1 and 2. 2. All bolts, nuts, cable assemblies, cable anchors, bearing plates,
- slot guards, struts, nails, pipes soil tubes and soil plates shall be galvanized.
- 3. The breakaway cable assembly must be taut. A locking device (vice grips or channel lock pliers) should be used to prevent cable from twisting when tightening nuts. 4. The wood blockouts shall be "toe nailed" to the rectangular wood posts to prevent them from turning when wood shrinks. The 2 nails required
- per blockout shall be 20 penny and galvanized. 5. For curb installation, the curb must end prior to post number 7. Where the curb is extended beyond post number 7, the flared SRT can not be used.
- A straight end treatment shall be used at the end of the straight guardrail that is placed at the face of the curb.
- 6. For details not shown, see the manufacturer's installation manual.
- 7. Minimum length of rail, including end terminal, in advance of fixed objects shall be 175 feet when the slotted rail terminal is used as the end terminal.

	NORTH DAKOTA NT OF TRANSPORTATION	This document was
	09-03-99	originally issued
	REVISIONS	and sealed by
DATE	CHANGE	MARK S GAYDOS,
03-15-01 06-29-01 12-06-02 04-23-03 12-01-04	Major revision Breakaway post added Added note 7 Revised note 7 PE Stamp added	Registration Number PE-4518, on 12/01/04 and the original document is stored at the Nort Dakota Department of Transportation